BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

SCHEDULE-B

NAME OF WORK: Improvements & Asphalting to Coconut Garden Layout roads of Mnajunatha Nagara in Bagalagunte in Ward No.14,

Sl. No	Description of work	Unit	Qty	Sanctioned Estimate Rates	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Earthwork excavation by manual means in Ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods Complete as per specification and direction of Engineer-in-charge of the work.	Cum	2496.5	65.88	Rupees Sixty Five and Eighty Eight Paise Only
2	Providing and laying in position plain cement concrete of mix M15 with OPC cement @240 kgs, with 40mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, Complete as per specification and direction of Engineer-in-charge of the work.	Cum	112.5	4675.32	Rupees Four Thousand Six Hundred Seventy Five and Thirty Two Paise Only
3	Providing and laying in position plain cement concrete of mix M20 with OPC cement @300 kgs, with 20mm and down size graded granite metal coarse aggregates @0.64cum and fine aggregates @0.43cum with superplastisiser @3lts Confirming to IS9103-1999 reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing Complete as per specification and direction of Engineer-in-charge of the work.	Cum	75	5323.32	Rupees Five Thousand Three Hundred Twenty Three and Thirty Two Paise Only
4	Construction of embankment with approved material Gravel/Murrum with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement Table 300-2 complete as per specifications. (which includes cost of gravel / murrum, watering charges & compaction by vibratory roller) Complete as per specification and direction of Engineer-in-charge of the work.	Cum	2271.5	166.32	Rupees One Hundred Sixty Six and Thirty Two Paise Only

EXECUTIVE ENGINEER-4
BBMP, DASARAHALLI DIVISION,
BANGALORE-560 010

Signature & Seal of the Contractor

EXECUTIVE ENGINEER
Bruhat Bangalore Mahanagara Palike
Dasarahalli Zone

Executive Engineer

5	Construction of granular sub-base by providing close g(ded material, mixing in mechaical mix plant at OMC carriage of mixed material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density Complete as per specification and direction of Engineer-in-charge of the work.	Cum	973.5	1060.56	Rupees One Thousand Sixty and Fifty Six Paise Only
6	Providing, laying, spreading and compacting graded stone aggregates to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. Specification No. 406 with all leads and lifts etc., Complete as per specification and direction of Engineer-in-charge of the work.	Cum	1622.5	1121.04	Rupees One Thousand One Hundred Twenty One and Four Paise Only
7	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading Complete as per specification and direction of Engineer-in-charge of the work.	Cum	2496.5	72.71	Rupees Seventy Two and Seventy One Paise Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION,
BANGALORE-560 010

Signature of the Contractor

EXECUTIVE ENGINEER
Executive Engineer,
Dasarahalli Division,
Bruhat Bangalore Mahanagara Palike,
Dasarahalli Zone, Bangalore-57.